

PanoVu Firmware

Version: V5.3.16

Release Note

Firmware Basic Information	Firmware Version:	V5.3.16 build170123
	SDK Version:	V5.2.6.10build20161201
	Play Library (PlayCtrl.dll)	V7.3.2.71_Build20161201
	Encapsulation Library	2.5.1.13_Build20161110
	(SystemTransform.dll)	
	iVMS-4200	v2.5.5.3 build20161213
	IE Client version	V4.0.1build161215

Hikvision Firmware V5.3.16 Features

1, Support model

• This firmware is for DS-2DP1636-D.

2, Newly add

Support panoramic view and original view model. Web component support TCP and HTTP live
 view. Client support TCP and RTSP over TCP.




Figure 1 Panoramic view






Figure 2 Original view

- Support mini SD card and NAS recording.
- Support video parameter configuration.
 - 1. Resolution: 2400*3840,1792*2880, 1600*2560, 1200*1920;
 - 2. Frame rate: up to 25fps@PAL, up to 24fps@NTSC.
 - 3. Support H.264. Video type support Video stream and video &audio stream.
- Support image parameters configuration.
- Support 7 alarm in and 2 alarm out. Support audio exception detection and exception.
- Support scheduled recording and capture. Scheduled capture function only capture original
 image, cannot capture panoramic image. Capture interval is recommended to more than 5s.
- Support record by web component and client. Playing record needs specific VSplayer.

Compatibility Update

- ISAPI version: V2.4;
- NVR Recommendation: I8 series V3.4.90 160926.



Customer Impact and Recommended Action

This update refers to function/compatibility improvement and will take effect automatically after the Date of Change. We are very sorry for any inconvenience of use-habit changes caused by this action. For any questions and request for this firmware, please contact our local technical support team.

Remarks:

- Hikvision reserves the right to change, alter or withdraw the above notification without prior notice.
- Product design and specifications are subject to change without prior notice.
- The Hikvision firmware may contain defects or errors known as errata which may cause the product to deviate from published specifications. Current characterized errata are available on request.
- Hikvision is not liable for any typing or printing errors.

Hikvision Digital Technology CO., Ltd.

No. 555 Qianmo Road, Binjiang District, Hangzhou 310051, China

Tel: +86-571-8807-5998 FAX: +86-571-8993-5635

Email: overseabusiness@hikvision.com